



LINCOLN PROFESSIONAL PARK

ANNEXATION MAP TO THE TOWN OF PARKER
SITUATED IN THE NORTHWEST 1/4 OF SECTION 15, TOWNSHIP 6 SOUTH, RANGE 66 WEST OF THE 6TH P.M.,
COUNTY OF DOUGLAS, STATE OF COLORADO
SHEET 1 OF 2



SUMMARY TABLE

TOTAL ANNEXATION AREA	190,643 SQ. FT. (4.38 AC.)
TOTAL ANNEXATION PERIMETER	1,750.99 FT.
ANNEXATION PERIMETER CONTIGUOUS TO PRESENT TOWN OF PARKER	1,750.99 FT. (100%)

LEGAL DESCRIPTION:

A PARCEL OF LAND SITUATED IN THE NORTHWEST QUARTER OF SECTION 15, TOWNSHIP 6 SOUTH, RANGE 66 WEST OF THE SIXTH PRINCIPAL MERIDIAN, COUNTY OF DOUGLAS, STATE OF COLORADO, MORE PARTICULARLY DESCRIBED AS FOLLOWS:

COMMENCING AT THE NORTHWEST CORNER OF SAID SECTION 15;
THENCE SOUTH 83°44'03" EAST, A DISTANCE OF 846.76 FEET TO A POINT ON THE SOUTH RIGHT-OF-WAY LINE OF LINCOLN AVENUE AND THE POINT OF BEGINNING;

THENCE ALONG SAID SOUTH RIGHT-OF-WAY LINE NORTH 89°29'00" EAST, A DISTANCE OF 371.25 FEET;
THENCE SOUTH 02°18'01" EAST, A DISTANCE OF 467.18 FEET TO A POINT ON THE NORTH LINE OF LOT 1, E.T. TECHNOLOGIES INC., RECORDED AT RECEPTION NO. 2002093991;
THENCE SOUTH 84°51'34" WEST ALONG SAID NORTH LINE, A DISTANCE OF 395.93 FEET TO A POINT ON THE EAST RIGHT-OF-WAY LINE OF DRANSFELDT ROAD DEEDED BY RECEPTION NO. 2002088425 AND A POINT OF NON-TANGENT CURVATURE;
THENCE ALONG SAID EAST RIGHT-OF-WAY LINE THE FOLLOWING SIX (6) COURSES:
1) ALONG THE ARC OF SAID CURVE TO THE RIGHT AN ARC LENGTH OF 25.79 FEET, SAID CURVE HAVING A RADIUS OF 660.00 FEET, A CENTRAL ANGLE OF 02°14'19", AND A CHORD WHICH BEARS NORTH 02°20'42" WEST A CHORD DISTANCE OF 25.79 FEET;
2) NORTH 01°13'32" WEST, A DISTANCE OF 165.71 FEET TO A POINT OF CURVATURE;
3) ALONG THE ARC OF SAID CURVE TO THE LEFT AN ARC LENGTH OF 43.04 FEET, SAID CURVE HAVING A RADIUS OF 740.00 FEET, A CENTRAL ANGLE OF 03°19'57", AND A CHORD WHICH BEARS NORTH 02°53'30" WEST A CHORD DISTANCE OF 43.03 FEET;
4) NORTH 04°33'29" WEST, A DISTANCE OF 217.83 FEET TO A POINT OF CURVATURE;
5) ALONG THE ARC OF SAID CURVE TO THE RIGHT AN ARC LENGTH OF 49.23 FEET, SAID CURVE HAVING A RADIUS OF 30.00 FEET, A CENTRAL ANGLE OF 94°01'51", AND A CHORD WHICH BEARS NORTH 42°27'27" EAST A CHORD DISTANCE OF 43.89 FEET;
6) NORTH 04°33'21" WEST, A DISTANCE OF 15.04 FEET TO THE POINT OF BEGINNING.

SAID PARCEL CONTAINS 190,643 SQUARE FEET OR 4.38 ACRES, MORE OR LESS.

PROFESSIONAL LAND SURVEYOR CERTIFICATION:

I, AARON MURPHY, A LICENSED PROFESSIONAL LAND SURVEYOR IN THE STATE OF COLORADO, DO HEREBY CERTIFY THAT THIS ANNEXATION MAP WAS PREPARED UNDER MY DIRECT SUPERVISION; THAT, TO THE BEST OF MY KNOWLEDGE AND BELIEF, THIS MAP ACCURATELY DELINEATES THE PARCEL OF LAND TO BE ANNEXED TO THE TOWN OF PARKER, COLORADO; AND THAT AT LEAST ONE SIXTH (1/6) OF THE BOUNDARY OF SAID PARCEL IS CONTIGUOUS TO THE PRESENT TOWN OF PARKER, COUNTY OF DOUGLAS, STATE OF COLORADO.

AARON MURPHY, PLS 38162 _____ DATE _____
FOR AND ON BEHALF OF
HARRIS KOCHER SMITH

TOWN COUNCIL ACCEPTANCE:

ACCEPTED BY THE PARKER TOWN COUNCIL ON THE ____ DAY OF _____, 20__

MAYOR, TOWN OF PARKER

ATTEST: _____
TOWN CLERK

NOTES:

- THIS SURVEY DOES NOT CONSTITUTE A TITLE SEARCH BY HARRIS KOCHER SMITH TO DETERMINE OWNERSHIP OR EASEMENTS OF RECORD. FOR ALL INFORMATION REGARDING EASEMENTS, RIGHTS-OF-WAY AND TITLE OF RECORD, HARRIS KOCHER SMITH RELIED UPON COMMITMENT FOR TITLE INSURANCE, COMMITMENT NO. NCS-1003894-KCTY ISSUED BY FIRST AMERICAN TITLE INSURANCE COMPANY AND HAVING AN EFFECTIVE DATE OF MARCH 02, 2020 AT 5:00 P.M. **THE SURVEYED PROPERTY IS A PORTION OF THE ABOVE REFERENCED TITLE COMMITMENT.**
- NOTICE: ACCORDING TO COLORADO LAW YOU MUST COMMENCE ANY LEGAL ACTION BASED UPON ANY DEFECT IN THIS SURVEY WITHIN THREE YEARS AFTER YOU FIRST DISCOVER SUCH DEFECT. IN NO EVENT MAY ANY ACTION BASED UPON ANY DEFECT IN THIS SURVEY BE COMMENCED MORE THAN TEN YEARS FROM THE DATE OF THE CERTIFICATION SHOWN HEREON.
- BASIS OF BEARINGS: BEARINGS ARE BASED ON THE NORTH LINE OF THE NORTHWEST QUARTER OF SECTION 15, TOWNSHIP 6 SOUTH, RANGE 66 WEST OF THE 6TH PRINCIPAL MERIDIAN. AS MONUMENTED AT BOTH THE NORTHWEST QUARTER CORNER AND NORTH QUARTER CORNER BY 3.25" ALUMINUM CAPS, ASSUMED TO BEAR SOUTH 89°29'00" WEST.
- SURVEYED PROPERTY FALLS WITHIN ZONE X OF THE FEDERAL EMERGENCY MANAGEMENT AGENCY FLOOD INSURANCE RATE MAP, MAP NO. 08035C0067G, LAST REVISED MARCH 16, 2016. ZONE X IS DEFINED AS AREAS OUTSIDE THE 0.2-PERCENT ANNUAL CHANCE FLOODPLAIN.
- THE LINEAR UNITS FOR THIS SURVEY ARE U.S. SURVEY FEET.
- THE SURVEYED PROPERTY IS SUBJECT TO THE TERMS, PROVISIONS, COVENANTS, CONDITIONS, RESTRICTIONS, OBLIGATIONS AND RESERVATIONS CONTAINED IN THE RECORDED DOCUMENTS IN THE TITLE COMMITMENT AS REFERENCED IN NOTE 1.

PROJECT CONTACTS:

DEVELOPER
PLAZA STREET FUND 106, LLC, A KANSAS LIMITED LIABILITY COMPANY,
2400 W. 75TH STREET, SUITE 220,
PRAIRIE VILLAGE, KANSAS 66208.

OWNER
HOWARD R PEASLEE & LEILA MAY PEASLEE RESIDUARY TRUST
426 FREEMONT DR
LAWRENCE, KS 66049

ENGINEER/SURVEYOR
HARRIS KOCHER SMITH,
1120 LINCOLN STREET, SUITE 1000,
DENVER, COLORADO 80203.

CLERK AND RECORDER CERTIFICATION:

STATE OF COLORADO)
) SS
COUNTY OF DOUGLAS)

I HEREBY CERTIFY THAT THIS MAP WAS FILED IN MY OFFICE ON THIS ____ DAY OF _____, 20__ A.D., AT A.M./P.M., AND WAS RECORDED AT RECEPTION NUMBER _____

COUNTY CLERK AND RECORDER

LINCOLN PROFESSIONAL PARK
ANNEXATION MAP TO THE TOWN OF PARKER

SHEET INDEX

SHEET 1	COVER
SHEET 2	SITE

PREPARED BY: _____ PROJECT #: 200829
HKS HARRIS KOCHER SMITH
1120 Lincoln Street, Suite 1000
Denver, Colorado 80203
P: 303.623.6300 F: 303.623.6311
HarrisKocherSmith.com

NO CHANGES ARE TO BE MADE TO THIS DRAWING WITHOUT WRITTEN PERMISSION OF HARRIS KOCHER SMITH.

FILEPATH: K:\020829\SURVEY\ANNX FLAT DWG LAYOUT LAYOUT
NO REFS
DATE PLOTTED: 03/03/2021 10:32:06A BY: HANMACDOUGAL

LINCOLN PROFESSIONAL PARK

ANNEXATION MAP TO THE TOWN OF PARKER
SITUATED IN THE NORTHWEST 1/4 OF SECTION 15, TOWNSHIP 6 SOUTH, RANGE 66 WEST OF THE 6TH P.M.,
COUNTY OF DOUGLAS, STATE OF COLORADO
SHEET 2 OF 2

POINT OF COMMENCEMENT
NW CORNER SECTION 15
FOUND 3.25" ALUM. CAP
STAMPED: T6S S.C. R66W
S9 S10 S15 S16
LS 19003 1999

NORTH QTR. CORNER SECTION 15
FOUND 3.25" ALUM. CAP
STAMPED: JR ENG T6S R66W
1/4 S10 S15 LS 30109

BASIS OF BEARINGS NORTH LINE NW 1/4 SEC 15 S89°29'00"W 2643.60'

NO CHANGES ARE TO BE MADE TO THIS DRAWING WITHOUT WRITTEN PERMISSION OF HARRIS KOCHER SMITH.


FILEPATH: K:\2008\2008SURVEY\ANNEX PLATTING LAYOUT.LAYOUT
NO REFS
DATE: 08/03/09 10:32:48A BY: HANNAK DOUGALL

WEST QTR COR SECTION 15
FOUND 3.25" ALUM. CAP
STAMPED: T6S R66W S16 S15
PLS 12405 1997

WEST LINE NW 1/4 SEC 15 S00°00'36"E 2670.43'

DRANSFELDT RD
(VARIABLE WIDTH
PUBLIC R.O.W.)

EXISTING ANNEXATION ORDINANCE 2.150
DRANSFELDT ROAD ROW ANNEXATION



UNPLATTED

11964 DRANSFELDT RD
OWNER: HOWARD R PEASLEE &
LEILA MAY PEASLEE RESIDUARY TRUST
PARCEL CONTAINS
190,643 SQ. FT. OR
4.38 AC. ±

UNPLATTED

OWNER: LINCOLN PROFESSIONAL PARK LP
EXISTING ANNEXATION ORDINANCE 2.198
LINCOLN PROFESSIONAL PARK LP
ANNEXATION

LEGEND


- FOUND MONUMENT AS DESCRIBED
- ▲ FOUND #5 REBAR WITH 1.25" ORANGE PLASTIC CAP PLS 25933
- SET #5 REBAR WITH 1.25" BLUE PLASTIC CAP PLS 38162 OR CONCRETE NAIL WITH 1" BRASS TAG PLS 38162
- ▨ ANNEXATION CONTIGUOUS TO TOWN OF PARKER

25' PARKER WATER AND
SANITATION DISTRICT ESMT.
BK. 342 PG. 897

EXISTING ANNEXATION ORDINANCE 2.138
ET TECHNOLOGIES PHASE II ANNEXATION

LOT 1, BLOCK 1
E.T. TECHNOLOGIES INC.
MINOR DEVELOPMENT PLAT
REC. NO. 2002089891

EXISTING ANNEXATION ORDINANCE 2.137
ET TECHNOLOGIES PHASE I ANNEXATION



SCALE: 1" = 30'

LINCOLN PROFESSIONAL PARK
ANNEXATION MAP TO THE TOWN OF PARKER

PREPARED BY: **HKS** HARRIS KOCHER SMITH
PROJECT #: 200829
1120 Lincoln Street, Suite 1000
Denver, Colorado 80203
P: 303.623.6300 F: 303.623.6311
HarrisKocherSmith.com