

Town of Parker CBMP Cost Opinion Spreadsheet

BMP No.	BMP	ID	Unit	Installation Unit Cost	Quantity	Cost
1	Check Dam	CD	LF	\$ 30.00		\$ -
2	Concrete Washout Area	CWA	EA	\$ 750.00	1	\$ 750.00
3	Construction Fence	CF	LF	\$ 2.00	946	\$ 1,892.00
4	Culvert Protection	CP	EA	\$120		\$ -
5	Detention Pond Protection	DP	EA	\$ 180.00		\$ -
6	Dewatering	D	EA	\$ 650.00		\$ -
7	Debris Trash Control	DC	HR	\$ 40.00		\$ -
8	Diversion Ditch	DD	LF	\$ 2.00		\$ -
9	Erosion Control Blanket	ECB	SY	\$ 2.10	148	\$ 310.80
10	Inlet Protection, Curb On Sump	IPCOS	EA	\$ 300.00	3	\$ 900.00
11	Inlet Protection, For Area Inlets Not In Pavement	IPAN	EA	\$ 290.00		\$ -
12	Inlet Protection, For Area Inlets In Pavement	IPAP	EA	\$ 350.00	1	\$ 350.00
13	Inlet Protection, Curb On-Grade	IPCOG	EA	\$ 180.00		\$ -
14	Lot Protection	LP	EA	\$ 800.00		\$ -
15	Masonry Work Protection	MWP	EA	\$ 250.00	1	\$ 250.00
16	Portable Toilet Protection	PTP	EA	\$ 75.00	3	\$ 225.00
17	Rough Cut Street Control	RCSC	EA	\$ 100.00		\$ -
18	Rock Sock	RS	LF	\$ 15.00		\$ -
19	Rock Sock in Swale	RSS	LF	\$ 20.00		\$ -
20	Straw Bale	SB	EA	\$ 20.00		\$ -
21	Temporary Sediment Basin	TSB	EA	\$2,500		\$ -
22	Sediment Control Log	SCL	LF	\$ 3.00	553	\$ 1,659.00
23	Silt Fence	SF	LF	\$ 1.25	652	\$ 815.00
24	Surface Roughening	SR	AC	\$ 175.00	1.16	\$ 203.00
25	Sidewalk Transition Protection	STP	EA	\$ 100.00		\$ -
26	Stabilized Staging Area	SSA	EA	\$ 500.00	1	\$ 500.00
27	Vehicle Tracking Control-VTC w/ Jersey Barriers	VTC	EA	\$ 1,750.00	1	\$ 1,750.00
28	Temporary Irrigation	TI	AC	\$30,000.00		\$ -
TOTAL						\$ 9,604.80