



10333 E. Dry Creek Road  
Suite 240  
Englewood, Colorado 80112  
720.482.9526 Fax 720.482.9546

## TRAILS AT CROWFOOT FILING 2 ENGINEER'S ESTIMATE OF ANTICIPATED COSTS

PROJECT: TRAILS AT CROWFOOT FILING 2  
CLIENT: E5X MANAGEMENT  
ESTIMATE PREPARED BY: CVL CONSULTANTS OF COLORADO, INC.


ACREAGE: 22.164  
LOTS: 101  
JOB NUMBER: 283701  
PHASE: FILING 2  
DATE: 12/5/2017

### SANITARY SEWER

ITEM	DESCRIPTION	QUANTITY	UNIT	COST/UNIT	TOTAL COST
	8" SEWER (PVC)	4,479	L.F.	\$48.00	\$214,992.00
	12" SEWER (PVC)	0	L.F.	\$54.00	\$0.00
	18" SEWER (PVC)	0	L.F.	\$67.00	\$0.00
	4' DIA. MANHOLE	24	EA.	\$2,850.00	\$68,400.00
	5' DIA. MANHOLE	0	EA.	\$2,850.00	\$0.00
	STANDARD CLEANOUT	0	EA.	\$300.00	\$0.00
	DROP MANHOLE	0	EA.	\$5,000.00	\$0.00
	INTERMEDIATE PLATFORM	0	EA.	\$700.00	\$0.00
	4" SEWER SERVICE	101	EA.	\$1,615.00	\$163,115.00
	20" STEEL CASING	0	L.F.	\$2,000.00	\$0.00
	CONNECTION TO EXISTING MAIN	1	EA.	\$1,900.00	\$1,900.00
					<b>\$448,407.00</b>

### WATERLINE

ITEM	DESCRIPTION	QUANTITY	UNIT	COST/UNIT	TOTAL COST
	6" WATERPIPE (DIP)	168	L.F.	\$20.00	\$3,360.00
	8" WATERPIPE (PVC)	4,845	L.F.	\$39.00	\$188,955.00
	12" WATERPIPE (PVC)	0	L.F.	\$57.00	\$0.00
	16" WATERPIPE (DIP)	0	L.F.	\$77.60	\$0.00
	6" GATE VALVE	9	EA.	\$1,000.00	\$9,000.00
	8" GATE VALVE	20	EA.	\$1,750.00	\$35,000.00
	12" GATE VALVE	0	EA.	\$3,000.00	\$0.00
	16" BUTTERFLY VALVE	0	EA.	\$18,000.00	\$0.00
	8" MISC. FITTINGS	30	EA.	\$460.00	\$13,800.00
	12" MISC. FITTINGS	0	EA.	\$730.00	\$0.00
	16" MISC. FITTINGS	0	EA.	\$1,500.00	\$0.00
	AIR / VACUUM VALVE	2	EA.	\$6,700.00	\$13,400.00
	8" CAP WITH BLOW OFF	7	EA.	\$2,000.00	\$14,000.00
	2" BLOW OFF VALVE (8" LINE-LOW POINT)	1	EA.	\$2,000.00	\$2,000.00
	6" BLOW OFF VALVE (16" LINE-LOW POINT)	0	EA.	\$2,500.00	\$0.00
	FIRE HYDRANT WITH 6" LEAD	8	EA.	\$5,000.00	\$40,000.00
	DEEP BURY FIRE HYDRANT WITH 6" LEAD	1	EA.	\$5,500.00	\$5,500.00
	IRRIGATION SERVICE W/ METER(2")	0	EA.	\$2,500.00	\$0.00
	DOMESTIC WATER SERVICE W/ METER	101	EA.	\$1,400.00	\$141,400.00
	20" STEEL CASING	0	L.F.	\$2,000.00	\$0.00
	CONNECTION TO EXISTING MAIN	6	EA.	\$1,000.00	\$6,000.00
					<b>\$472,415.00</b>



CONTINGENCIES 20% OF CONSTRUCTION COSTS = \$184,164.40

**Total Filing 2 Water/Sewer= \$1,104,986.40**