



CVL Consultants of Colorado, Inc.  
 10333 E. Dry Creek Rd  
 Suite 240  
 Englewood, Colorado 80112  
 720.482.9526 Fax 720.482.9546

**ENGINEERS PUBLIC IMPROVEMENT COST ESTIMATE  
 TRAILS AT CROWFOOT FILING 6  
 12/5/2017**

**ROADWAY**

No.	Description	Quantity	Unit	Cost/Unit	Total Cost
	6" VERTICAL CURB & GUTTER (2' PAN)	0	L.F.	\$22.00	\$0.00
	6" VERTICAL CURB & GUTTER (1' PAN)	0	L.F.	\$22.00	\$0.00
	4" MOUNTABLE CURB & GUTTER	3,274	L.F.	\$24.00	\$78,576.00
	HOT MIX ASPHALT PAVEMENT (5" DEPTH)	5,457	S.Y.	\$23.50	\$128,231.67
	CONCRETE PAVEMENT	0	S.Y.	\$90.00	\$0.00
	AGGRIGATE BASE COURSE	1,455	C.Y.	\$40.50	\$58,932.00
	SUBGRADE STABILIZATION	1,455	S.Y.	\$2.10	\$3,055.73
	ROADWAY SUBGRADE PREP (EXTEND 2' OUTSIDE CURB)	1,455	S.Y.	\$1.25	\$1,818.89
	5' DETACHED CONCRETE SIDEWALK	3,274	L.F.	\$27.00	\$88,398.00
	SIDEWALK SUBGRADE PREP (MIN 1' OUTSIDE LIMITS)	2,546	S.Y.	\$1.25	\$3,183.06
	CORNER CURB RAMP (INCLUDES SUBGRADE PREP)	0	EA.	\$2,200.00	\$0.00
	MIDBLOCK CURB RAMP (INCLUDES SUBGRADE PREP)	0	EA.	\$2,200.00	\$0.00
	CROSS PAN (INCLUDES SUBGRADE PREP)	0	S.Y.	\$103.50	\$0.00
	TRENCH DRAIN	0	L.F.	\$19.00	\$0.00
	MEDIAN COVER	0	S.Y.	\$90.00	\$0.00
	ADJUST MANHOLE	6	EA.	\$760.00	\$4,560.00
	ADJUST WATER VALVE	0	EA.	\$425.00	\$0.00
Total Cost					<b>\$366,755.34</b>

**STRIPING**

Item	Description	Quantity	Unit	Cost/Unit	Total Cost
	LONG LINE EPOXY PVMT. MARKING	0	GAL	\$105.00	\$0.00
	CROSSWALK BAR	0	S.F.	\$8.00	\$0.00
	STOP BAR	0	S.F.	\$0.93	\$0.00
	ARROW	0	EA.	\$120.00	\$0.00
Total Cost					<b>\$0.00</b>

**SIGNAGE (INCLUDE POST AND ANCHOR)**

Item	Description	Quantity	Unit	Cost/Unit	Total Cost
	STREET NAME SIGN WITH STOP SIGN	5	EA.	\$530.00	\$2,650.00
	GROUND SIGN	0	EA.	\$280.00	\$0.00
	TYPE III BARRICADE	0	EA.	\$2,500.00	\$0.00
	SPECIAL SIGN	0	EA.	\$280.00	\$0.00
Total Cost					<b>\$2,650.00</b>

**DRAINAGE AND STORMWATER IMPROVMENTS**

Item	Description	Quantity	Unit	Cost/Unit	Total Cost
	18" RCP	0	L.F.	\$64.00	\$0.00
	24" RCP	0	L.F.	\$83.00	\$0.00
	30" RCP	0	L.F.	\$100.00	\$0.00
	36" RCP	0	L.F.	\$136.00	\$0.00
	48" RCP	0	L.F.	\$200.00	\$0.00
	30" FES WITH CONCRETE CUTOFF WALL	0	EA.	\$2,400.00	\$0.00
	36" FES WITH CONCRETE CUTOFF WALL	0	EA.	\$3,000.00	\$0.00
	48" FES WITH CONCRETE CUTOFF WALL	0	EA.	\$3,400.00	\$0.00
	4' MANHOLE	0	EA.	\$2,500.00	\$0.00
	5' MANHOLE	0	EA.	\$3,070.00	\$0.00
	6' MANHOLE	0	EA.	\$4,380.00	\$0.00
	5' TYPE R INLET	0	EA.	\$9,000.00	\$0.00
	10' TYPE R INLET (SPECIFIC ON 10" INCREMENT)	0	EA.	\$10,700.00	\$0.00
	15' TYPE R INLET	0	EA.	\$11,000.00	\$0.00
Total Cost					<b>\$0.00</b>

**PUBLIC IMPROVMENTS (TOWN) SUBTOTAL \$369,405.34**

CONSTRUCTION CONTINGENCY (10%) \$36,940.53  
 MOBILIZATION (5%) \$18,470.27  
 SURVEYING (3%) \$11,082.16  
 CONSTRUCTION MANAGEMENT & TESTING (12%) \$44,328.64

**PUBLIC IMPROVEMENT TOTAL \$480,226.95**

**SECURITY AT 110% = \$528,249.64**