



10333 E. Dry Creek Road
Suite 240
Englewood, Colorado 80112
720.482.9526 Fax 720.482.9546

TRAILS AT CROWFOOT FILING 14 ENGINEER'S ESTIMATE OF ANTICIPATED COSTS

PROJECT:	TRAILS AT CROWFOOT FILING 14	ACREAGE:	9.06
CLIENT:	HR 935, LLC	LOTS:	50
ESTIMATE PREPARED BY:	CVL CONSULTANTS OF COLORADO, INC.	JOB NUMBER:	283701
		PHASE:	FILING 14
		DATE:	10/26/2018

SANITARY SEWER

ITEM	DESCRIPTION	QUANTITY	UNIT	COST/UNIT	TOTAL COST
	8" SEWER (PVC)	1,568	L.F.	\$48.00	\$75,264.00
	12" SEWER (PVC)	0	L.F.	\$54.00	\$0.00
	18" SEWER (PVC)	0	L.F.	\$67.00	\$0.00
	4' DIA. MANHOLE	12	EA.	\$2,850.00	\$34,200.00
	5' DIA. MANHOLE	0	EA.	\$2,850.00	\$0.00
	STANDARD CLEANOUT	0	EA.	\$300.00	\$0.00
	DROP MANHOLE	0	EA.	\$5,000.00	\$0.00
	INTERMEDIATE PLATFORM	0	EA.	\$700.00	\$0.00
	4" SEWER SERVICE	36	EA.	\$1,615.00	\$58,140.00
	20" STEEL CASING	0	L.F.	\$2,000.00	\$0.00
	CONNECTION TO EXISTING MAIN	1	EA.	\$1,900.00	\$1,900.00
					\$169,504.00

WATERLINE

ITEM	DESCRIPTION	QUANTITY	UNIT	COST/UNIT	TOTAL COST
	6" WATERPIPE (DIP)	118	L.F.	\$20.00	\$2,360.00
	8" WATERPIPE (PVC)	2,040	L.F.	\$39.00	\$79,560.00
	12" WATERPIPE (PVC)	0	L.F.	\$57.00	\$0.00
	16" WATERPIPE (DIP)	0	L.F.	\$77.60	\$0.00
	6" GATE VALVE	6	EA.	\$1,000.00	\$6,000.00
	8" GATE VALVE	10	EA.	\$1,750.00	\$17,500.00
	12" GATE VALVE	0	EA.	\$3,000.00	\$0.00
	16" BUTTERFLY VALVE	0	EA.	\$18,000.00	\$0.00
	8" MISC. FITTINGS	12	EA.	\$460.00	\$5,520.00
	12" MISC. FITTINGS	0	EA.	\$730.00	\$0.00
	16" MISC. FITTINGS	0	EA.	\$1,500.00	\$0.00
	AIR / VACUUM VALVE	2	EA.	\$6,700.00	\$13,400.00
	8" CAP WITH BLOW OFF	4	EA.	\$2,000.00	\$8,000.00
	2" BLOW OFF VALVE (8" LINE-LOW POINT)	0	EA.	\$2,000.00	\$0.00
	6" BLOW OFF VALVE (16" LINE-LOW POINT)	0	EA.	\$2,500.00	\$0.00
	FIRE HYDRANT WITH 6" LEAD	6	EA.	\$5,000.00	\$30,000.00
	DEEP BURY FIRE HYDRANT WITH 6" LEAD	0	EA.	\$5,500.00	\$0.00
	IRRIGATION SERVICE W/ METER(2")	1	EA.	\$2,500.00	\$2,500.00
	DOMESTIC WATER SERVICE W/ METER	50	EA.	\$1,400.00	\$70,000.00
	20" STEEL CASING	0	L.F.	\$2,000.00	\$0.00
	CONNECTION TO EXISTING MAIN	2	EA.	\$1,000.00	\$2,000.00
					\$236,840.00

CONTINGENCIES 20% OF CONSTRUCTION COSTS = \$81,268.80

Total Filing 14 Water/Sewer= **\$487,612.80**

