



10333 E. Dry Creek Road
 Suite 240
 Englewood, Colorado 80112
 720.482.9526 Fax 720.482.9546

TRAILS AT CROWFOOT FILING 15 ENGINEER'S ESTIMATE OF ANTICIPATED COSTS

PROJECT:	ACREAGE:	9.171
TRAILS AT CROWFOOT FILING 15	LOTS:	44
CLIENT:	JOB NUMBER:	283701
HR 935, LLC	PHASE:	FILING 15
ESTIMATE PREPARED BY:	DATE:	6/28/2018
CVL CONSULTANTS OF COLORADO, INC.		

SANITARY SEWER

ITEM	DESCRIPTION	QUANTITY	UNIT	COST/UNIT	TOTAL COST
	8" SEWER (PVC)	1,490	L.F.	\$48.00	\$71,520.00
	12" SEWER (PVC)	0	L.F.	\$54.00	\$0.00
	18" SEWER (PVC)	0	L.F.	\$67.00	\$0.00
	4' DIA. MANHOLE	14	EA.	\$2,850.00	\$39,900.00
	5' DIA. MANHOLE	0	EA.	\$2,850.00	\$0.00
	STANDARD CLEANOUT	0	EA.	\$300.00	\$0.00
	DROP MANHOLE	0	EA.	\$5,000.00	\$0.00
	INTERMEDIATE PLATFORM	0	EA.	\$700.00	\$0.00
	4" SEWER SERVICE	30	EA.	\$1,615.00	\$48,450.00
	20" STEEL CASING	0	L.F.	\$2,000.00	\$0.00
	CONNECTION TO EXISTING MAIN	1	EA.	\$1,900.00	\$1,900.00
					\$161,770.00

WATERLINE

ITEM	DESCRIPTION	QUANTITY	UNIT	COST/UNIT	TOTAL COST
	6" WATERPIPE (DIP)	72	L.F.	\$20.00	\$1,440.00
	8" WATERPIPE (PVC)	2,037	L.F.	\$39.00	\$79,443.00
	12" WATERPIPE (PVC)	0	L.F.	\$57.00	\$0.00
	16" WATERPIPE (DIP)	0	L.F.	\$77.60	\$0.00
	6" GATE VALVE	4	EA.	\$1,000.00	\$4,000.00
	8" GATE VALVE	0	EA.	\$1,750.00	\$0.00
	12" GATE VALVE	0	EA.	\$3,000.00	\$0.00
	16" BUTTERFLY VALVE	0	EA.	\$18,000.00	\$0.00
	8" MISC. FITTINGS	22	EA.	\$460.00	\$10,120.00
	12" MISC. FITTINGS	0	EA.	\$730.00	\$0.00
	16" MISC. FITTINGS	0	EA.	\$1,500.00	\$0.00
	AIR / VACUUM VALVE	0	EA.	\$6,700.00	\$0.00
	8" CAP WITH BLOW OFF	4	EA.	\$2,000.00	\$8,000.00
	2" BLOW OFF VALVE (8" LINE-LOW POINT)	0	EA.	\$2,000.00	\$0.00
	6" BLOW OFF VALVE (16" LINE-LOW POINT)	0	EA.	\$2,500.00	\$0.00
	FIRE HYDRANT WITH 6" LEAD	4	EA.	\$5,000.00	\$20,000.00
	DEEP BURY FIRE HYDRANT WITH 6" LEAD	0	EA.	\$5,500.00	\$0.00
	IRRIGATION SERVICE W/ METER(2")	1	EA.	\$2,500.00	\$2,500.00
	DOMESTIC WATER SERVICE W/ METER	44	EA.	\$1,400.00	\$61,600.00
	20" STEEL CASING	0	L.F.	\$2,000.00	\$0.00
	CONNECTION TO EXISTING MAIN	2	EA.	\$1,000.00	\$2,000.00
					\$189,103.00

CONTINGENCIES 20% OF CONSTRUCTION COSTS = **\$70,174.60**

Total Filing 2 Water/Sewer= \$421,047.60